

**AGENDA ITEM**  
**June 21, 2016**

Subject: Water main replacement on North Indiana

Department: Public Works

While preparing North Indiana for curb/gutter we discovered that the water main was not at sufficient depth and the thin walled 8" PVC pipe was laying on solid rock without proper bedding. These conditions make the line vulnerable to breaks and leaks; the line needed to be replaced. The replacement cost of the 8" water main for materials only is \$11,534.20. Due to the depth of only 12 to 18 inches of cover we need to relocate the main and services before the new curb/gutter can be finished.